

Lp.	Podst	Opis i wyliczenia	j.m.	Poszcz	Razem
1	KNR 2-01 0301-02	Ręczne roboty ziemne z transportem urobku samochodami samowyladowczymi (kat.gr.III) (0.30*0.80*0.60)*4	m ³ m ³	0.576	
				RAZEM	0.576
2	KNR 2-02 0205-01	Płyty fundamentowe żelbetowe (0.30*0.76*0.90)*4	m ³ m ³	0.821	
				RAZEM	0.821
3	KNR 2-02 0290-04	Przygotowanie i montaż zbrojenia konstrukcji monolit.budowli - pręty żebrowane ((0.76*3*0.888)/1000)*2*4 ((4*0.30*0.888)/1000)*2*4	t t t	0.016 0.009	
				RAZEM	0.025
4	KNR 2-02 1217-05	Obramienia z kątownika 40x40x4 mm (0.30+0.30+0.76+0.76)*4	m m	8.480	
				RAZEM	8.480